CASTLE ROCK

SHADY OAK
CASTLE ROCK

GEOLOGY
sandstone - quarried in USA

COLOR RANGE
tan, cream, gold, orange
and occasional gray and black

CONSISTENCY PER PALLET
somewhat consistent

PALLET AMOUNTS
FULL VENEER (sold/ton) 4,000lbs each
THIN VENEER (sold/each) QB or BX
QUANTITY BOX - QB
1 - 100 sq ft of flats
1 - 50 lin ft of corners
SMALL BOX - BX
24 - 8 sq ft flat boxes, 192 total ft
20 - 8 lin ft corner boxes, 160 total feet

ASTM TESTING DATA
SHADY OAK C97
water absorption—2.83%
SHADY OAK C97
specific gravity—2.50

FULL VENEER

COMMON COVERAGE

Standard Joint	Drystack	Overgrout
40 ft²/ ton	30 ft²/ton	50 ft²/ton

DIMENSIONS
l: 6” to 42” (16”)
h: 4” to 12”
w: 3” to 5” (4”)
Stone ends shall be no less than 2-1/2” width

TYPICAL PIECE
Ends square; split top, bottom, and sides; bedface face and back; stone is squares and rectangles.

THIN VENEER

COMMON COVERAGE

Standard Joint	Drystack	Overgrout
8 & 100 square feet	6 & 75 ft²	10 & 110 ft²

DIMENSIONS
l: 4” to 24” (14”)
h: 4” to 12”
w: 3/4” to 1-1/4” (1”)
corner return 3” to 5”

TYPICAL PIECE
Ends square; split top, bottom, and sides; bedface face and sawn back; stone is squares and rectangles.

PART NUMBERS
FULL VENEER:
1-FV-1118-TN
THIN VENEER:
QB flat: 1-TF-1118-QB
BX flat: 1-TF-1118-BX
QB corner: 1-TC-1118-QB
BX corner: 1-TC-1118-BX

ARCHITECT/DESIGNER INFO
INSTALLATION SHOWN
Mortar: Laticrete MVIS
Joint Type: Drystack

BIM DETAILS - SCAN
Revit, Hatch Patterns, Seamless Textures, 3-Part Specs, DWGS, SDS, Warranty