# MOSAIC
*JUTE CLOTH WEBWALL*

## GEOLOGY
limestone - quarried in USA

## COLOR RANGE
tans, browns, light grays, and whites

## CONSISTENCY PER PALLET
somewhat consistent

## PALLET AMOUNTS
FULL VENEER (sold/ton) 4,000lbs each
THIN VENEER (sold/each) QB or BX
- QUANTITY BOX - QB
  - 1 - 100 sq ft of flats
  - 1 - 50 lin ft of corners
- SMALL BOX - BX
  - 24 - 8 sq ft flat boxes, 192 total ft
  - 20 - 8 lin ft corner boxes, 160 total feet

## ASTM TESTING DATA
JUTE CLOTH C97
- water absorption—10.03%
- specific gravity — 1.995 to 2.008
- density—125.1 lbs/ft3

JUTE CLOTH C170
- dry perpendicular—4,040 psi
- wet perpendicular—1,830 psi
- dry parallel —3,210 psi
- wet parallel—1,480 psi

JUTE CLOTH C880
- flexural strength -wet —440 psi
- flexural strength -dry —600 psi

## PART NUMBERS
FULL VENEER:
- 1-FV-1102-TN

THIN VENEER:
- QB flat: 1-TF-1102-QB
- BX flat: 1-TF-1102-BX
- QB corner: 1-TC-1102-QB
- BX corner: 1-TC-1102-BX

## ARCHITECT/DESIGNER INFO
INSTALLATION SHOWN
- Mortar: Quikrete Type S
- Joint Type: Raked

BIM DETAILS - SCAN
Revit, Hatch Patterns, Seamless Textures, 3-Part Specs, DWGS, SDS, Warranty

## FULL VENEER
COMMON COVERAGE

| Standard Joint | Drystack | Overgrout |
|---|---|---|
| 40 ft$^2$/ ton | 30 ft$^2$/ton | 50 ft$^2$/ton |

DIMENSIONS
l: 3” to 16” dia.
h: 3” to 16” dia.
w: 3” to 5” (4”)
note: lengths and heights are irregular shapes 3 inches to 16 inches in diameter

TYPICAL PIECE
Ends irregular; natural split sides; bedface face and back; stone is random shapes.

## THIN VENEER
COMMON COVERAGE

| Standard Joint | Drystack | Overgrout |
|---|---|---|
| 8 & 100 square feet | 6 & 75 ft$^2$ | 10 & 110 ft$^2$ |

DIMENSIONS
l: 3” to 16” dia.
h: 3” to 16” dia.
w: 3/4” to 1-1/4” (1”)
corner return 3” to 6”
note: lengths and heights are irregular shapes 3 inches to 12 inches in diameter

TYPICAL PIECE
Ends irregular; natural split sides; bedface face and sawn back; stone is random shapes.